

**MT Statewide Phase4
B22 LIDAR
PROCESSING
REPORT**

Project ID: 231442

Work Unit: 300196

2023

Submitted: May 16, 2023

Prepared by:

Prepared for:



Contents

| | |
|---|-----------|
| 1. Summary / Scope | 4 |
| 1.1. Summary | 4 |
| 1.2. Scope | 4 |
| 1.3. Coverage | 4 |
| 1.4. Duration | 4 |
| 1.5. Issues..... | 4 |
| 2. Planning / Equipment | 7 |
| 2.1. Flight Planning..... | 7 |
| 2.2. LiDAR Sensor | 8 |
| 2.3. Aircraft | 10 |
| 2.4. Time Period | 12 |
| 3. Processing Summary..... | 12 |
| 3.1. Flight Logs | 13 |
| 3.2. LiDAR Processing..... | 14 |
| 3.3. LAS Classification Scheme | 16 |
| 3.4. Classified LAS Processing..... | 17 |
| 3.5. Hydro-Flattened Breakline Processing | 18 |
| 3.6. Hydro-Flattened Raster DEM Processing | 19 |
| 3.7. Intensity Image Processing | 20 |
| 3.8. Swath Separation Raster Processing | 21 |
| 3.9. Maximum Surface Height Raster Processing | 22 |
| 3.10. Contour Processing | 23 |
| 4. Project Coverage Verification..... | 25 |
| 5. Accuracy Testing..... | 26 |
| 5.1. Horizontal Accuracy..... | 26 |
| 5.2. Relative Vertical Accuracy | 27 |
| Project Report Appendices | i |
| Appendix A | ii |
| Flight Logs | ii |
| Appendix B..... | v |
| POSPac Graphics | v |

List of Figures

| | |
|---|----|
| Figure 1. Work Unit Boundary | 6 |
| Figure 2. Billings QL2 Trajectories | 7 |
| Figure 3. Riegl VQ1560i LiDAR Sensor Specifications | 8 |
| Figure 4. AXIS Plane VulcanAir P-68C (N89LT) | 10 |
| Figure 5. AXIS Plane Piper Navajo PA-31 (N359RX) | 11 |
| Figure 6. Work Unit 300196 Bare-Earth DEMs | 19 |
| Figure 7. Work Unit 300196 Intensity Images..... | 20 |
| Figure 8. Work Unit 300196 SSI Images..... | 21 |
| Figure 9. Work Unit 300196 MSHR Images | 22 |
| Figure 10. LiDAR Tile Layout | 24 |
| Figure 11. Work Unit 300197 LiDAR Coverage..... | 25 |

List of Tables

| | |
|--|----|
| Table 1. Originally Planned LiDAR Specifications | 4 |
| Table 2. LiDAR System Specifications..... | 9 |
| Table 3. Lifts for QL2 Billings | 11 |
| Table 4. Software Versions | 15 |
| Table 5. LAS Classifications | 16 |

List of Appendices

Appendix A: Flight Logs

Appendix B: POSPac Graphics

1. Summary / Scope

1.1. Summary

This report contains a summary of the Montana Phase4 B22, Work Unit 300196 LiDAR acquisition task order, issued by USGS under their Contract 140G0221D0016 on May 6, 2022. This Work Unit yielded a project area covering 3600 square miles over Montana at Quality Level 2. The intent of this document is only to provide specific validation information for the data acquisition/collection, processing, and production of deliverables completed as specified in the task order.

1.2. Scope

Aerial topographic LiDAR was acquired using state of the art technology along with the necessary surveyed ground control points (GCPs) and airborne GPS and inertial navigation systems. The aerial data collection was designed with the following specifications listed in Table 1 below.

Table 1. Originally Planned LiDAR Specifications

| Average Point Density | Flight Altitude (AGL) | Field of View | Minimum Side Overlap | RMSEz |
|------------------------|-----------------------|---------------|----------------------|---------|
| 2 pts / m ² | 1798 m | 58.5° | 30% | ≤ 10 cm |

1.3. Coverage

The Work Unit boundary covers 3600 square miles over Montana. Project extents are shown in Figure 1.

1.4. Duration

LiDAR data was acquired from July 8, 2022, to August 12, 2022, in 13 total lifts. See Section: 2.4. Time Period for more details.

1.5. Issues

No issues encountered during acquisition or processing that resulted in data anomalies.

MT Statewide Phase4 B22 Work Unit 300196

Projected Coordinate System:

State Plane Montana FIPS 2500

Horizontal Datum: NAD83 (2011)

Vertical Datum: NAVD88 (GEOID 18)

Units: Meters

| | |
|-------------------|--|
| LiDAR Point Cloud | Classified Point Cloud in .LAS 1.4 format |
| Rasters | <ul style="list-style-type: none"> • 1-meter Hydro-flattened Bare-earth Digital Elevation Model (DEM) in GeoTIFF format • 1-meter Intensity images in GeoTIFF format • 2-meter Swath Separation Images • 1-meter Maximum Surface Height Raster |
| Vectors (*.shp) | <ul style="list-style-type: none"> • Project Boundary • LiDAR Tile Index • Continuous Hydro-flattened Breaklines • Flightline Swath |
| Reports (*.pdf) | <ul style="list-style-type: none"> • LiDAR Mapping Report |
| Metadata (*.xml) | <ul style="list-style-type: none"> • Breaklines • Classified Point Cloud • DEM • Intensity Imagery • Contours |

MT Statewide Phase4 QL2 Work Unit 300196 Boundary




Figure 1. Work Unit Boundary

2. Planning / Equipment

2.1. Flight Planning

Flight planning was based on the unique project requirements and characteristics of the project site. The basis of planning included: required accuracies, type of development, amount / type of vegetation within project area, required data posting, and potential altitude restrictions for flights in project vicinity.

Detailed project flight planning calculations were performed for the project using RiPARAMETER planning software.




Figure 2. Billings QL2 Trajectories

2.2. LiDAR Sensor

AXIS Geospatial utilized a Riegl VQ1560i LiDAR sensor, serial number 2222593, for data acquisition.

The Riegl 1560i system is a dual channel waveform processing airborne scanning system. It has a laser pulse repetition rate of up to 2 MHz resulting in up to 600 lines per second. The system utilizes an integrated IMU/GNSS unit.

A summary of the aerial acquisition parameters for the project are shown in the LiDAR System Specifications in Table 2.

| | |
|-------------------------------|---|
| Minimum Range ^[8] | 100 m |
| Accuracy ^{[9][10]} | 20 mm |
| Precision ^{[10][11]} | 20 mm |
| Laser Pulse Repetition Rate | up to 2 MHz |
| Effective Measurement Rate | up to 1.33 MHz @ 60° scan angle |
| Echo Signal Intensity | provided for each echo signal |
| Laser Wavelength | near infrared |
| Laser Beam Divergence | ≤ 0.18 mrad @ 1/e ^[12] , ≤ 0.25 mrad @ 1/e ² ^[13] |
| Number of Targets per Pulse | with online waveform processing: practically unlimited ^{[14][15]} monitoring data output: first pulse |
| Scanner Performance | |
| Scanning Mechanism | rotating polygon mirror |
| Scan Pattern | parallel scan lines per channel, crossed scan lines between channels |
| Tilt Angle of Scan Lines | ± 14° = 28° |
| Forward/ Backward Scan Angle | ± 8° at the edges |
| in Non-Nadir Direction | 60° total per channel, resulting in an effective FOV of 58° |
| Scan Angle Range | 40 ^[16] - 600 lines/sec |
| Total Scan Rate | 0.006° ≤ Δθ ≤ 0.180° ^{[17][18]} |
| Angular Step Width Δθ | 0.001° |
| Angle Measurement Resolution | |

Figure 3. Riegl VQ1560i LiDAR Sensor Specifications

| | | Riegl VQ1560i (SN2222593 and SN2223544) |
|------------------------------|--------------------------|---|
| Terrain and Aircraft Scanner | | Flying Height |
| Scanner | Recommended Ground Speed | 155 kts |
| | Field of View | 58.5° |
| Laser | Scan Rate Setting Used | 2 x 132 lps |
| Coverage | Laser Pulse Rate Used | 2 x 700 kHz |
| Point Spacing and Density | Full Swath Width | 2015 m |
| | Line Spacing | 0.58 m |
| Point Spacing and Density | Average Point Spacing | 0.71 m |
| | Average Point Density | 2 pts / m ² |

Table 2. LiDAR System Specifications

2.3. Aircraft

All flights for the project were accomplished using customized aircraft. Plane type and tail numbers are listed below.

LiDAR Collection Planes

- VulcanAir P-68C (small twin engine), Tail Number(s): N89LT
- Piper Navajo PA-31 (twin engine), Tail Number(s): N359RX

These aircraft provided an ideal, stable aerial base for LiDAR acquisition. These aerial platforms have relatively fast cruise speeds, which are beneficial for project mobilization / demobilization while maintaining relatively slow stall speeds, proving ideal for collection of high-density, consistent data posting using a state-of-the-art Riegl LiDAR system.



Figure 4. AXIS Plane VulcanAir P-68C (N89LT)



Figure 5. AXIS Plane Piper Navajo PA-31 (N359RX)

2.4. Time Period

Project specific flights were conducted between July 8, 2022, and August 12, 2022. Fourteen aircraft lifts were completed. Accomplished lifts are listed below.

| Lift | Start UTC | End UTC |
|------------------------------|---------------------|---------------------|
| 06302022 (SN2222593, N89LT) | 06/30/2022 12:10 PM | 06/30/2022 1:01 PM |
| 07082022 (SN2222593, N89LT) | 07/08/2022 12:00 PM | 07/08/2022 4:20 PM |
| 07092022 (SN2222593, N89LT) | 07/09/2022 3:32 PM | 07/09/2022 4:24 PM |
| 07102022 (SN2222593, N89LT) | 07/10/2022 8:11 AM | 07/10/2022 12:56 PM |
| 07122022 (SN2222593, N89LT) | 07/12/2022 8:29 AM | 07/12/2022 1:22 PM |
| 07132022 (SN2222593, N89LT) | 07/13/2022 8:16 AM | 07/13/2022 12:46 PM |
| 07282022 (SN2223544, N359RX) | 07/28/2022 1:38 PM | 07/28/2022 6:38 PM |
| 07292022 (SN2222593, N89LT) | 07/29/2022 4:36 PM | 07/29/2022 6:12 PM |
| 07302022 (SN2222593, N89LT) | 07/30/2022 1:37 PM | 07/30/2022 5:03 PM |
| 07312022 (SN2222593, N89LT) | 07/31/2022 1:34 PM | 07/31/2022 7:42 PM |
| 08012022 (SN2222593, N89LT) | 08/01/2022 1:28 PM | 08/01/2022 4:46 PM |
| 08042022 (SN2222593, N89LT) | 08/04/2022 1:16 PM | 08/04/2022 6:11 PM |
| 08052022 (SN2222593, N359RX) | 08/05/2022 2:34 PM | 08/05/2022 7:11 PM |
| 08092022 (SN2222593, N359RX) | 08/09/2022 1:58 PM | 08/09/2022 4:42 PM |

Table 3. Lifts for QL2 Billings

3. Processing Summary

3.1. Flight Logs

Flight logs were completed by LiDAR sensor technicians for each mission during acquisition. These logs depict a variety of information, including:

- Job / Project #
- Flight Date / Lift Number
- Scan Rate (HZ)
- Pulse Rate Frequency (Hz)
- Ground Speed
- Altitude
- Flight Line #
- Flight Line Start and Stop Times
- Flight Line Altitude (AMSL)
- Heading
- Speed
- Notes (includes visibility, winds, ride, weather, temperature, dew point, pressure, etc.)

Project specific flight logs for each sortie are available in Appendix A.

3.2. LiDAR Processing

Applanix + POSPac software was used for post-processing of airborne GPS and inertial data (IMU), which is critical to the positioning and orientation of the LiDAR sensor during all flights. Applanix POSPac combines aircraft raw trajectory data with stationary GPS base station data yielding a “Smoothed Best Estimate Trajectory” (SBET) necessary for additional post processing software to develop the resulting geo-referenced point cloud from the LiDAR missions.

During the sensor trajectory processing (combining GPS & IMU datasets) certain statistical graphs and tables are generated within the Applanix POSPac processing environment which are commonly used as indicators of processing stability and accuracy. This data for analysis includes max horizontal / vertical GPS variance, separation plot, altitude plot, PDOP plot, processing mode, number of satellite vehicles, and mission trajectory.

Project specific POSPac graphics for each mission are available in Appendix B.

Point clouds were created using the RiPROCESS software. The generated point cloud is the mathematical three dimensional composite of all returns from all laser pulses as determined from the aerial mission. The point cloud is imported into TerraSolid distributive processing software. Imported data is tiled and then calibrated using TerraMatch. Using TerraScan, the vertical accuracy of the surveyed ground control is tested, and any bias is removed from the data. TerraScan and TerraModeler are then used for automated data classification and manual cleanup.

Actual acquired point density has been evaluated and confirmed to meet USGS standards for the relevant Quality Level. LAStools is used to calculate point density and spacing average per swath. Additional checks are made by loading LAS data directly into TerraScan and sampling open, flat areas in the acquired LAS.

After verification of accuracy and point density are complete, the calibration phase begins. Terrasolid is used to analyze and test data for discrepancies between overlapping flightlines. Tie Lines or representations of the dense lidar point cloud per scanner along every swath. Tie Lines are used to determine the best correction solution for Heading/Roll/Pitch, to eliminate or minimize discrepancies, resulting in a highly accurate and seamless transition between flight lines.

DEM's and Intensity Images are then generated using TerraScan and Global Mapper software. In the bare-earth surface model, above-ground features are excluded from the data set. Global Mapper is used as a final check of the bare-earth dataset.

Swath Separation images at the required Quality Level are generated to confirm the calibration corrections that have been applied and data meets USGS standards. Overlapping flightlines are used to compare the elevation differences between flightlines and colorized to show any differences larger than the tolerances described in the latest Lidar Base Specification. This colorization is overlaid onto the existing Intensity images for each tile.

Finally, proprietary software is used to perform statistical analysis of the LAS files.

| Software | Version |
|-------------------|-----------|
| Applanix + POSPac | 8.6 |
| RiPROCESS | 1.8.6 |
| Global Mapper | 23.1;24.1 |
| TerraModeler | 21.008 |
| TerraScan | 22.007 |
| TerraMatch | 22.008 |

Table 4. Software Versions

3.3. LAS Classification Scheme

Classification is determined by LiDAR Base Specification 2022, Revision A and are an industry standard for the processing of LiDAR point clouds. All data start the process as Class 1 (Unclassified). Then classification is determined through automated classification routines utilizing TerraScan macro processing.

The classes used in the dataset are as follows and have the following descriptions:

| | Classification Name | Description |
|----|-----------------------------|---|
| 1 | Processed, but Unclassified | Laser returns that are not included in the ground class, or any other project classification |
| 2 | Bare-Earth | Laser returns that are determined to be ground using automated and manual cleaning algorithms |
| 7 | Low Noise | Laser returns that are often associated with scattering from reflective surfaces, or artificial points below the ground surface |
| 9 | Water | Laser returns that are found inside of hydro features |
| 17 | Bridge Deck | Laser returns falling on bridge decks |
| 18 | High Noise | Laser returns that are often associated with birds or artificial points above the ground surface |
| 20 | Ignored Ground | Ground points that fall within the given threshold of a collected hydro feature. |

Table 5. LAS Classifications

3.4. Classified LAS Processing

The bare-earth class is then manually reviewed to ensure correct classification of Class 2 (Ground) points. Individual TerraScan routines are combined to form an overall macro to segment and classify the LiDAR point cloud. The key focus of these routines is the accurate classification of bare earth ground points. Automated macros are run that classify most of the point cloud. Visual QC and edits are performed to ensure automated techniques worked properly and that data confirms to USGS Quality Level standards. After the initial automated bare earth surface is established, hydro collection begins through heads up digitizing, utilizing the bare earth surface and intensity information.

All ground (ASPRS Class 2) LiDAR data inside of the lake / ponds and Double Line Drain hydro flattening breaklines were classified to water (ASPRS Class 9) using TerraScan macro functionality. A buffer of 0.5 meters was used around each hydro flattened feature to classify these ground (ASPRS Class 2) points to ignored ground (ASPRS Class 20). All lake / ponds Island and Double Line Drain Island features were checked to ensure that the ground (ASPRS Class 2) points were reclassified to the correct class of Water after the automated classification was completed. These classes were created through automated processes only and were verified for classification accuracy via visual inspection.

Any noise that was identified either through manual review or automated routines was classified to the appropriate class (ASPRS Class 7 and/or ASPRS Class 18) followed by flagging as withheld bit for those points.

All data was manually reviewed, and any remaining artifacts removed, using functionality provided by TerraScan and TerraModeler. Global Mapper is used as a final check of the bare-earth dataset. TerraScan was then used to create the deliverable industry standard LAS files for all point cloud data. Global Mapper, along with LP360 software, was used to perform final statistical analysis of the classes in the LAS files, on a per tile level to verify final classification metrics and full LAS header information.

3.5. Hydro-Flattened Breakline Processing

Using heads-up digitization, all hydro breaklines are collected for lakes/ponds greater than 2 acres in size and inland streams and rivers with a width of 30 meters or greater. Islands greater than 1 acre in size within a collected hydro feature were also captured. LiDAR intensity imagery and bare-earth surface models are used to ensure appropriate and complete collection of these features.

Breakline vector data was then draped to the ground surface elevation. Lakes/ponds were set to an appropriate, single elevation to allow for the generation of hydro-flattened digital elevation models (DEM). Double Line Drain elevations are assigned based on LiDAR elevations and surrounding terrain features to ensure all breaklines match the LiDAR within acceptable tolerances. Some deviation is expected between breaklines and LiDAR elevations due to monotonicity, connectivity, and flattening rules that are enforced on the breaklines. Once completeness, horizontal placement, and vertical variances are reviewed, all breaklines are evaluated for topological consistency and data integrity using a combination of ESRI's ArcGIS, Global Mapper, and manual review of hydro-flattened DEMs.

Breaklines are combined into one seamless shapefile, clipped to the project boundary, and imported into an Esri file geodatabase.

3.6. Hydro-Flattened Raster DEM Processing

Hydro-Flattened DEMs (topographic) represent a LiDAR-derived product illustrating the grounded terrain and associated breaklines (*as described above*) in raster form. Global Mapper was used to take all input sources (bare-earth LiDAR points, bridge and hydro breaklines, etc.) and create a Triangulated Irregular Network (TIN) on a tile-by-tile basis. Data extending past the tile edge is incorporated in this process so proper triangulation can occur. From the TIN, linear interpolation is used to calculate the cell values for the raster product. The raster product is then clipped back to the tile edge ensuring no overlapping cells remain across the project area. A 32-bit floating point GeoTIFF DEM is generated for each tile with a pixel size of 1 meter. AXIS Geospatial's proprietary software is then used to write appropriate horizontal and vertical projection information as well as applicable header values into the file during product generation. Each DEM is reviewed in Global Mapper to check for any surface anomalies and to ensure a seamless dataset. AXIS Geospatial uses a proprietary tool to check all formatting requirements of the DEMs to meet specifications.

GDAL version 3.1.4, was used to populate and verify that the correct CRS was applied to all files.




Figure 6. Work Unit 300196 Bare-Earth DEM

3.7. Intensity Image Processing

Intensity images represent reflectivity values collected by the LiDAR sensor during acquisition. TerraScan was used to export intensity images at 1 meter resolution. Intensity images were produced as 8-bit, 256 grayscale images in GeoTiff format. Appropriate horizontal projection information as well as applicable header values were written during product generation.




Figure 7. Work Unit 300196 Intensity Images

3.8. Swath Separation Raster Processing

Swath Separation Imagery was produced for the entire project area. Swath separation images use color-coding to illustrate differences in elevation (z-) values where swaths overlap. The color-coded images are semi-transparent and overlay the LiDAR intensity image. They are ancillary data used as visual aids to identify regions more easily within point cloud datasets that may have suspect interswath alignment or other geometric issues. Imagery was created using last returns with all classification and bit flags, except for noise and withheld bit flag are included. Images are derived from a TIN and have a 50% transparent RGB layer over lidar intensity. Color intervals are as follows for QL2 data: 0-8cm, green; 8-16cm, yellow; >16cm, red. These files were produced as GeoTIFF tiles using a cell size of 2 meters. SSI are generated from the point cloud data and will not be altered after creation, nor will there be further maintenance on this product. Appropriate horizontal projection information as well as applicable header values are written to the file during product generation. AXIS Geospatial uses a proprietary tool to check all formatting requirements of the images against specifications.




Figure 8. Work Unit 300196 Swath Separation Images

3.9. Maximum Surface Height Raster Processing

Maximum Surface Height rasters (topographic) represent a LiDAR-derived product illustrating natural and built-up features. Global Mapper is used to take all first-return classified LiDAR points, excluding those flagged with a withheld bit, to create a raster on a tile-by-tile basis. Data extending past the tile edge is incorporated in this process so that proper gridding can occur. The raster product is then clipped back to the tile edge so that no overlapping cells remain across the project area. A 32-bit floating point GeoTIFF is generated for each tile with a pixel size of 1 meter. GDAL was used to write appropriate horizontal and vertical projection information as well as applicable header values into the file after product generation. Each maximum surface height raster was reviewed in Global Mapper to check for any anomalies and to ensure a seamless dataset. AXIS Geospatial uses a proprietary tool to check all formatting requirements of the DEMs against specifications.




Figure 9. Work Unit 300196 MSHR Images

3.10. Contour Processing

The LAS Ground Class, along with breakline data, was used to create a surface of hydro flattened bare-earth DEMs. Contours were produced at 1-foot intervals in shapefile format using Global Mapper. Automated smoothing techniques were applied. No manual editing of contours was performed. Contours were attributed with every fifth contour as Index and all others as Intermediate. Contours were cut into 1000 m by 1000 m tiles to match the LAS and Bare-earth DEM deliverables. Tiled contour shapefiles were combined into one continuous dataset within an Esri File Geodatabase. There are no spot elevations or depressions on separate layers.

MT Statewide Phase4 B22 Work Unit 300196 Tile Layout




Figure 10. LiDAR Tile Layout

4. Project Coverage Verification

4.1. Swath Polygon Boundaries

Swath polygons of each flightline, depicting the boundary of LiDAR points, are exported using LAStools. These swath polygons were reviewed against the project boundary to verify adequate project coverage. *Please refer to Figure 11.*




Figure 11. Work Unit 300196 LiDAR Coverage

5. Geometric Accuracy

5.1. Horizontal Accuracy

LiDAR horizontal accuracy is a function of Global Navigation Satellite System (GNSS) derived positional error, flying altitude, and INS derived attitude error. The obtained RMSE_r value is multiplied by a conversion factor of 1.7308 to yield the horizontal component of the National Standards for Spatial Data Accuracy (NSSDA) reporting standard where a theoretical point will fall within the obtained radius 95% of the time. Based on a flying altitude of 1798 meters, an IMU error of 0.0025 decimal degrees, and a GNSS positional error of 0.05 meters, this project was compiled to meet 0.25 meter horizontal accuracy at 95% confidence level. A summary is shown below.

| Horizontal Accuracy | |
|---------------------|---------|
| RMSE _r | 0.49 ft |
| | 0.15 m |
| ACC _r | 0.82 ft |
| | 0.25 m |

5.2. Relative Vertical Accuracy

Relative vertical accuracy refers to the internal consistency of the data set as a whole: the ability to place an object in the same location given multiple flight lines, GPS conditions, and aircraft attitudes. When the LiDAR system is well calibrated, the swath-to-swath vertical divergence is low (<0.08 meters). The relative vertical accuracy was computed by comparing the ground surface model of each individual flight line with its neighbors in overlapping regions. The average (mean) line to line relative vertical accuracy for the MT Statewide Phase4 B22 project was -0.0043 feet (-0.0013 meters). A summary is shown below.

| Relative Vertical Accuracy | |
|----------------------------------|-------------------------|
| Sample | 50 flight line surfaces |
| Average | -0.0043 ft |
| | -0.0013 m |
| Median | -0.0082 ft |
| | -0.0025 m |
| RMSE | 0.141 ft |
| | 0.043 m |
| Standard Deviation (1σ) | 0.013 ft |
| | 0.004 m |
| 1.96σ | 0.029 ft |
| | 0.0087 m |

Project Report Appendices

**The following section contains the appendices as listed in
the MT Statewide Phase4 B22 LiDAR Project Report.**

Flight Logs

| | | | | | | | | | | | | | | | | | | |
|--------------------|-----------|--------|-----|------------|-----------|--------------------|-------|-------------------|---------|---------|---------|---|---------------------------|-----|--|--------|----------|---------------|
| MOB START | 7:30 | 3183.0 | BIL | PECK | | | 13:50 | 3188.8 | BIL | PECK | | | 0:00 | 0.0 | | | | 0:00 |
| t on station | 8:30 | 3183.9 | | TOT | 5.8 | | | | | TOT | -3188.8 | | | | | TOT | 0.0 | |
| t off station | 13:05 | 3188.5 | | MSN | 4.6 | | | | | MSN | 0.0 | | | | | MSN | 0.0 | |
| MOB END | 13:25 | 3188.8 | BIL | MOB | 1.2 | | | | BIL | MOB | -3188.8 | | | | | MOB | 0.0 | |
| Line # | Direction | Start | End | Start Time | Stop Time | Altitude (Planned) | | Altitude (Actual) | | Remarks | | 0 | 0 | | | Clouds | Aperture | Shutter Speed |
| | | | | MTN ZONE | | | | | | | | | | | | | | |
| BILLINGS WEST: Q 2 | | | | | | | | | 700 X 2 | 100% | 155 KTS | | 5900' | | | | | |
| X 68 | S 163 | | | 12:10 | 12:14 | | | 11214 | | | | | | | | | | |
| 67 | W 252 | | | 12:20 | 12:29 | | | 10840 | | | | | Yellowstone River | | | | | |
| 66 | E 72 | | | 12:31 | 12:39 | | | 10824 | | | | | GETTING CHOPPY -west MTNs | | | | | |
| 65 | W 252 | | | 12:42 | 12:50 | | | 10824 | | | | | | | | | | |
| 64 | E 72 | | | 12:54 | 13:01 | | | 10824 | | | | | choppy / end of fuel | | | | | |
| | | | | | | | | | | | | | too choppy, end of day | | | | | |

| axis geospatial | | | | LiDAR and Imagery Flight Report | | | | | | | Project(s): | | 20220708_LT_II_STTC_PM | | | | | |
|-------------------------------|----------------|--------|-----------------|---------------------------------|-----------|--------------------|-------------|----------------------|-----------|--|---------------------|------------------------|------------------------|--------|---------|---------|----------|---------------|
| Pilot: | JT | | | Project Number(s): | | | see below | | | | Date: | 20220708_LT_II_STTC_PM | | | | | | |
| Operator: | PM | | | Project Name(s): | | | see below | | | | Mission Start (LT): | 11:55 | | | | | | |
| Aircraft: | N89LT | | | Hobbs Start: | 3191.5 | | Hobbs Stop: | | | 3196.0 | Mission End (LT): | 16:28 | | | | | | |
| LiDAR Unit: | VQ-1560i - II | | | Scan Rate: | | | | Camera Unit: | | Phase One | | Drive: | VQ II L2 | | | | | |
| MTA Zones: | | | | Grnd Spd Max (kts): | 155 kts | | | FOV (deg): | | 58.52 | | Sun Angle: | >30° | | | | | |
| PRR (kHz): | 700 x 2 | | | Altitude (feet AMT): | 5950' | | | Lateral Overlap (%): | | | | Lens: | 50mm | | | | | |
| Laser Power (%): | 100% | | | Point Spacing (m): | | | | Forward Overlap (%): | | | | Point Density (ppms): | | | | | | |
| | Camera Counter | | Line Start/Stop | | | | | | | | | | | | | | | |
| | Time | Hobbs | 20078-21b | | | | Time | Hobbs | 20078-21b | | | Time | Hobbs | | | | | |
| MOB START | 11:15 | 3190.9 | BIL | Billings East | | | 16:55 | 3196.3 | BIL | Billings East | | | 8:45 | 3190.9 | | | 0:00 | |
| t on station | 11:55 | 3191.5 | | TOT | 5.4 | | | | TOT | -5.4 | | | | | TOT | -3190.9 | | |
| t off station | 16:28 | 3196.0 | | MSN | 4.5 | | | | MSN | 0.0 | | | | | MSN | 0.0 | | |
| MOB END | 16:55 | 3196.3 | BIL | MOB | 0.9 | | 8:45 | 3190.9 | BIL | MOB | -5.4 | | | | MOB | -3190.9 | | |
| Line # | Direction | Start | End | Start Time | Stop Time | Altitude (Planned) | | Altitude (Actual) | | Remarks | | 0 | 0 | | | Clouds | Aperture | Shutter Speed |
| | | | | MTN ZONE | | | | | | | | | | | | | | |
| 20078: Montana: Billings East | | | | | | | | | | | | | | | | | | |
| 72 | N 351 | | | 12:00 | 12:14 | | | 9600 | | 700 X 2 | 100% | 5900' | 155 kts | | 134 LPS | | | |
| 73 | S 171 | | | 12:17 | 12:32 | | | 9587 | | clouds / virga, had to keep heading east | | | | | | | | |
| 74 | N 351 | | | 12:35 | 12:49 | | | 9583 | | 171° vs 184° YAW / CRAB !! - southbound = 13° | | | | | | | | |
| 75 | S 171 | | | 12:55 | 13:12 | | | 9570 | | wind / mtn wave - difficult to maintain att / head | | | | | | | | |
| 76 | N 351 | | | 13:15 | 13:31 | | | 9564 | | a little hazy // lines collected looked ok | | | | | | | | |
| 77 | S 171 | | | 13:34 | 13:49 | | | 9547 | | | | | | | | | | |
| 78 | N 351 | | | 13:52 | 14:07 | | | 9534 | | air becoming more volatile | | | | | | | | |
| 79 | S 171 | | | 14:10 | 14:25 | | | 9554 | | more turb north | | | | | | | | |
| 80 | N 351 | | | 14:28 | 14:41 | | | 9514 | | north rougher | | | | | | | | |
| 81 | S 171 | | | 14:44 | 14:57 | | | 9505 | | | | | | | | | | |
| 82 | N 351 | | | 15:00 | 15:12 | | | 9524 | | | | | | | | | | |
| 83 | S 171 | | | 15:15 | 15:25 | | | 9514 | | | | | | | | | | |
| 84 | N 351 | | | 15:28 | 15:37 | | | 9508 | | bumpy | | | | | | | | |
| 85 | S 171 | | | 15:41 | 15:50 | | | 9455 | | bumpy | | | | | | | | |
| 86 | N 351 | | | 15:53 | 16:01 | | | 9432 | | bumpy / chops | | | | | | | | |
| 87 | S 171 | | | 16:03 | 16:11 | | | 9436 | | | | | | | | | | |
| 88 | N 351 | | | 16:14 | 16:17 | | | 9357 | | | | | | | | | | |
| 89 | W 261 | | | 16:20 | | | | 9495 | | | | | | | | | | |

| axis geospatial | | | | LiDAR and Imagery Flight Report | | | | | Project(s): | | 20220709_LT_II_STTC_PM | | | | |
|-------------------------------|----------------|--------|-----------------|---------------------------------|-----------|--------------------|-------------------|---|-------------|---------------------|------------------------|-----------------------|----------|----------|---------------|
| Pilot: | JT | | | Project Number(s): | | | see below | | | Date: | 20220709_LT_II_STTC_PM | | | | |
| Operator: | PM | | | Project Name(s): | | | see below | | | Mission Start (LT): | 8:45 | | | | |
| Aircraft: | N89LT | | | Hobbs Start: | 3197.4 | Hobbs Stop: | 3202.1 | | | | Mission End (LT): | 13:30 | | | |
| LIDAR Unit: | VQ-1560 - II | | | Scan Rate: | | | | Camera Unit: | Phase One | | | Drive: | VQ II L3 | | |
| MTA Zones: | | | | Grnd Spd Max (kts): | 155 kts | | | FOV (deg): | 58.52 | | | Sun Angle: | > 30° | | |
| PRR (kHz): | 700 x 2 | | | Altitude (feet AMT): | 5900' | | | Lateral Overlap (%): | | | | Lens: | 50mm | | |
| Laser Power (%): | 100% | | | Point Spacing (m): | | | | Forward Overlap (%): | | | | Point Density (ppms): | | | |
| | Camera Counter | | Line Start/Stop | | | | | | | | | | | | |
| | Time | Hobbs | 20078-21b | | | Time | Hobbs | 20078-21b | | | Time | Hobbs | | | |
| MOB START | 7:35 | 3196.3 | BIL | PECK | | 14:35 | 3202.7 | MLS | BILL EAST | | 16:50 | 3204.9 | | Time | |
| t on station | 8:45 | 3197.4 | | TOT | 6.4 | 15:30 | 3203.6 | | TOT | 2.2 | | | TOT | -3204.9 | |
| t off station | 13:30 | 3202.1 | | MSN | 4.7 | 16:25 | 3204.5 | | MSN | 0.9 | | | MSN | 0.0 | |
| MOB END | 14:00 | 3202.7 | MLS | MOB | 1.7 | 16:50 | 3204.9 | BIL | MOB | 1.3 | | | MOB | -3204.9 | |
| Line # | Direction | Start | End | Start Time | Stop Time | Altitude (Planned) | Altitude (Actual) | | | Remarks | 0 | 0 | Clouds | Aperture | Shutter Speed |
| | | | | MTN ZONE | | | | | | | | | | | |
| 20078: Montana: BILLINGS EAST | | | | | | | | | | | | | | | |
| 71 | S 172 | | | 15:32 | 15:49 | | 9593 | 700 X 2 | 100% | 5900' | 155 kts | 134 LPS | | | |
| 70 | N 351 | | | 15:56 | 16:08 | | 9587 | 160 kt grp at south start of line / nose high | | | | | | | |
| | | | | | | | | air getting choppy | | | | | | | |
| 89 | W 261 | | | 16:22 | 16:24 | | 9495 | Please QC overlap for these - thx | | | | | | | |

| axis geospatial | | | | LiDAR and Imagery Flight Report | | | | | Project(s): | | 20220710_LT_II_STTC_PM | | | | |
|-------------------------------|----------------|--------|-----------------|---------------------------------|-----------|--------------------|-------------------|------------------------------------|-------------|---------------------|------------------------|-----------------------|----------|----------|---------------|
| Pilot: | JT | | | Project Number(s): | | | see below | | | Date: | 20220710_LT_II_STTC_PM | | | | |
| Operator: | PM | | | Project Name(s): | | | see below | | | Mission Start (LT): | 8:10 | | | | |
| Aircraft: | N89LT | | | Hobbs Start: | 3205.3 | Hobbs Stop: | 3209.4 | | | | Mission End (LT): | 12:10 | | | |
| LIDAR Unit: | VQ-1560 - II | | | Scan Rate: | | | | Camera Unit: | Phase One | | | Drive: | VQ II L3 | | |
| MTA Zones: | | | | Grnd Spd Max (kts): | 155 kts | | | FOV (deg): | 58.52 | | | Sun Angle: | > 30° | | |
| PRR (kHz): | 700 x 2 | | | Altitude (feet AMT): | 5900' | | | Lateral Overlap (%): | | | | Lens: | 50mm | | |
| Laser Power (%): | 100% | | | Point Spacing (m): | | | | Forward Overlap (%): | | | | Point Density (ppms): | | | |
| | Camera Counter | | Line Start/Stop | | | | | | | | | | | | |
| | Time | Hobbs | 20078-21b | | | Time | Hobbs | 20078-21b | | | Time | Hobbs | | Time | |
| MOB START | 7:35 | 3204.9 | BIL | BILL EAST | | 12:15 | 3209.5 | 0 | BILL WEST | | 13:20 | 3210.5 | | Time | |
| t on station | 8:10 | 3205.3 | | TOT | 4.6 | 12:25 | 3209.6 | | TOT | 1.0 | | | TOT | -3210.5 | |
| t off station | 12:10 | 3209.4 | | MSN | 4.1 | 13:00 | 3210.1 | | MSN | 0.5 | | | MSN | 0.0 | |
| MOB END | 12:15 | 3209.5 | | MOB | 0.5 | 13:20 | 3210.5 | BIL | MOB | 0.5 | | | MOB | -3210.5 | |
| Line # | Direction | Start | End | Start Time | Stop Time | Altitude (Planned) | Altitude (Actual) | | | Remarks | 0 | 0 | Clouds | Aperture | Shutter Speed |
| | | | | MTN ZONE | | | | | | | | | | | |
| 20078: Montana: BILLINGS EAST | | | | | | | | | | | | | | | |
| 69 | N 351 | | | 8:11 | 8:27 | | 9600 | 700 X 2 | 100% | 5900' | 155 kts | 134 LPS | | | |
| 68 | S 171 | | | 8:30 | 8:44 | | 9613 | 190° YAW SOUTHBOUND / 171° PLANNED | | | | | | | |
| 67 | N 351 | | | 8:48 | 9:03 | | 9603 | | | | | | | | |
| 66 | S 171 | | | 9:07 | 9:20 | | 9629 | | | | | | | | |
| 65 | N 351 | | | 9:23 | 9:37 | | 9623 | chopp starting to begin | | | | | | | |
| 64 | S 171 | | | 9:40 | 9:53 | | 9636 | 185° | | | | | | | |
| 63 | N 351 | | | 9:58 | 10:14 | | 9639 | air getting a lil more active | | | | | | | |
| 60 | S 171 | | | 10:16 | 10:29 | | 9646 | nose up 10 ° major down draft | | | | | | | |
| 58 | N 351 | | | 10:33 | 10:47 | | 9669 | | | | | | | | |
| 56 | S 171 | | | 10:51 | 11:04 | | 9665 | | | | | | | | |
| 54 | N 351 | | | 11:07 | 11:20 | | 9659 | | | | | | | | |
| 52 | S 171 | | | 11:25 | 11:38 | | 9652 | getting more rough throughout | | | | | | | |
| 50 | N 351 | | | 11:41 | 11:55 | | 9672 | getting too rough, going to x tie | | | | | | | |
| X 59 | E 81 | | | 12:04 | 12:09 | | 9495 | | | | | | | | |
| | | | | | | | | | | | | | | | |
| 20078: Montana: BILLINGS WEST | | | | | | | | | | | | | | | |
| X 59 | W 261 | | | 12:28 | 12:32 | | 10413 | 700 X 2 | 100% | 5900' | 155 kts | 134 LPS | | | |
| 57 | S 171 | | | 12:35 | 12:45 | | 10089 | YAW CRAB: 190° / 170° | | | | | | | |
| 56 | N 351 | | | 12:48 | 12:56 | | 10112 | | | | | | | | |
| | | | | | | | | conditions / chop too rough | | | | | | | |
| | | | | | | | | clouds popping all around | | | | | | | |

| MOB START | 7:40 | 3211.1 | BIL | BILL EAST | | | 13:45 | 3217.0 | BIL | BILL WEST | | | 0:00 | 0.0 | | | |
|-------------------------------|-----------|--------|-----|------------|-----------|--|--------------------|--------|-------------------|-------------------------------------|---------|-------|---------|---------|---------|--|--------|
| ton station | 8:25 | 3211.8 | | TOT 5.9 | | | | | | TOT -3217.0 | | | | | TOT 0.0 | | |
| toff station | 13:25 | 3216.7 | | MSN 4.9 | | | | | | MSN 0.0 | | | | | MSN 0.0 | | |
| MOB END | 13:45 | 3217.0 | BIL | MOB 1.0 | | | | | BIL | MOB -3217.0 | | | | | MOB 0.0 | | |
| Line # | Direction | Start | End | Start Time | Stop Time | | Altitude (Planned) | | Altitude (Actual) | | Remarks | 0 | 0 | | | | Clouds |
| | | | | MTN ZONE | | | | | | | | | | | | | |
| 20078: Montana: BILLINGS EAST | | | | | | | | | | | | | | | | | |
| 48 | N 351 | | | 8:29 | 8:43 | | | 9685 | | 700 X 2 | 100% | 5900' | 155 kts | 134 LPS | | | |
| 46 | S 171 | | | 8:46 | 9:01 | | | 9642 | | long line waiting take off | | | | | | | |
| 44 | N 351 | | | 9:04 | 9:18 | | | 9685 | | southbound YAW = 181° / 171° | | | | | | | |
| 42 | S 171 | | | 9:21 | 9:36 | | | 9682 | | | | | | | | | |
| 40 | N 351 | | | 9:39 | 9:52 | | | 9675 | | | | | | | | | |
| 38 | S 171 | | | 9:55 | 10:09 | | | 9679 | | | | | | | | | |
| 36 | N 351 | | | 10:13 | 10:26 | | | 9688 | | | | | | | | | |
| 34 | S 171 | | | 10:29 | 10:43 | | | 9669 | | | | | | | | | |
| 32 | N 351 | | | 10:47 | 11:00 | | | 9767 | | mild chop starting - north end line | | | | | | | |
| 30 | S 171 | | | 11:04 | 11:17 | | | 9751 | | | | | | | | | |
| 28 | N 351 | | | 11:20 | 11:33 | | | 9793 | | last mile in north - rough / bumpy | | | | | | | |
| 26 | S 171 | | | 11:37 | 11:48 | | | 9829 | | north - rough / bumpy | | | | | | | |
| 24 | N 351 | | | 11:51 | 12:02 | | | 9885 | | 7 nm - : - north - rough / bumpy | | | | | | | |
| 22 | S 171 | | | 12:06 | 12:14 | | | 9898 | | | | | | | | | |
| 20 | N 351 | | | 12:17 | 12:24 | | | 9948 | | | | | | | | | |
| 18 | S 171 | | | 12:27 | 12:35 | | | 9967 | | | | | | | | | |
| 16 | N 351 | | | 12:38 | 12:46 | | | 9944 | | | | | | | | | |
| 14 | S 171 | | | 12:49 | 12:58 | | | 9997 | | | | | | | | | |
| 12 | N 351 | | | 13:01 | 13:09 | | | 10026 | | | | | | | | | |
| X 89 | E 81 | | | 13:14 | 13:22 | | | 9495 | | bump n chops | | | | | | | |
| | | | | | | | | | | clouds building to the south | | | | | | | |

| axis geospatial | | | | LiDAR and Imagery Flight Report | | | | | | Project(s): | | 20220713_LT_II_STTC_PM | | | | | |
|-------------------------------|---|--------|----------------------|---------------------------------|-----------|--------------------|----------------------|-----------|-----------|---|------------------------|------------------------|---------|----------|---------------|--|--|
| Pilot: | JT | | | Project Number(s): | | see below | | | | Date: | 20220713_LT_II_STTC_PM | | | | | | |
| Operator: | PM | | | Project Name(s): | | see below | | | | Mission Start (LT): | 8:15 | | | | | | |
| Aircraft: | N89LT | | | Hobbs Start: | 3217.5 | | Hobbs Stop: | 3222.1 | | Mission End (LT): | 12:50 | | | | | | |
| LiDAR Unit: | VQ-1560I - II | | Scan Rate: | 155 kts | | | Camera Unit: | Phase One | | | Drive: | VQ II L3 | | | | | |
| MTA Zones: | 700 x 2 | | Grnd Spd Max (kts): | 5950' | | | FOV (deg): | 58.52 | | Sun Angle: | > 30° | | | | | | |
| PRR (kHz): | 100% | | Altitude (feet AMT): | 100% | | | Lateral Overlap (%): | 100% | | Lens: | 50mm | | | | | | |
| Laser Power (%): | Point Spacing (m): | | Forward Overlap (%): | Point Density (ppms): | | | | | | | | | | | | | |
| | Camera Counter | | Line Start/Stop | | | | | | | | | | | | | | |
| | Time | Hobbs | 20078-21b | | | | Time | Hobbs | 20078-21b | | | | Time | Hobbs | | | |
| MOB START | 7:35 | 3217.0 | BIL | BILL EAST | | | 13:30 | 3222.3 | BIL | BILL EAST | | | 14:40 | 3223.4 | | | |
| t on station | 8:15 | 3217.5 | | TOT | 5.3 | | 14:00 | 3222.8 | | TOT | 1.1 | | | TOT | -3223.4 | | |
| t off station | 12:50 | 3222.1 | | MSN | 4.6 | | 14:20 | 3223.1 | | MSN | 0.3 | | | MSN | 0.0 | | |
| MOB END | 13:05 | 3222.3 | BIL | MOB | 0.7 | | 14:40 | 3223.4 | BIL | MOB | 0.8 | | | MOB | -3223.4 | | |
| Line # | Direction | Start | End | Start Time | Stop Time | Altitude (Planned) | Altitude (Actual) | Remarks | 0 | 0 | | | Clouds | Aperture | Shutter Speed | | |
| | | | | MTN ZONE | | | | | | | | | | | | | |
| 20078: Montana: BILLINGS EAST | | | | | | | | | | | | | | | | | |
| XX 62 | first record - too close to line, still climbing, DNU | | | | | | | | 700 X 2 | 100% | 5900' | 155 kts | 134 LPS | | | | |
| 62 | S 171 | | | 8:16 | 8:24 | | | | 10125 | | | | | | | | |
| 61 | N 351 | | | 8:28 | 8:36 | | | | 10148 | | | | | | | | |
| 59 | S 171 | | | 8:39 | 8:48 | | | | 10154 | | | | | | | | |
| 57 | N 351 | | | 8:51 | 8:59 | | | | 10190 | | | | | | | | |
| 55 | S 171 | | | 9:02 | 9:11 | | | | 10213 | | | | | | | | |
| 53 | N 351 | | | 9:14 | 9:22 | | | | 10289 | | | | | | | | |
| 51 | S 171 | | | 9:26 | 9:34 | | | | 10345 | | | | | | | | |
| 49 | N 351 | | | 9:38 | 9:46 | | | | 10299 | | | | | | | | |
| 47 | S 171 | | | 9:49 | 9:59 | | | | 10240 | | | | | | | | |
| 45 | N 351 | | | 10:02 | 10:10 | | | | 10171 | | | | | | | | |
| 43 | S 171 | | | 10:14 | 10:23 | | | | 10085 | | | | | | | | |
| 41 | N 351 | | | 10:26 | 10:34 | | | | 10007 | | | | | | | | |
| 39 | S 171 | | | 10:38 | 10:47 | | | | 9948 | | | | | | | | |
| 37 | N 351 | | | 10:50 | 10:59 | | | | 9961 | | | | | | | | |
| 35 | S 171 | | | 11:02 | 11:13 | | | | 10026 | | | | | | | | |
| 33 | N 351 | | | 11:16 | 11:25 | | | | 10108 | | | | | | | | |
| 31 | S 171 | | | 11:28 | 11:38 | | | | 10128 | | | | | | | | |
| 29 | N 351 | | | 11:41 | 11:51 | | | | 9951 | | | | | | | | |
| 27 | S 171 | | | 11:55 | 12:05 | | | | 9984 | | | | | | | | |
| 25 | N 351 | | | 12:08 | 12:17 | | | | 9925 | ...and the chop begins (at least in south turn) | | | | | | | |
| 23 | S 171 | | | 12:21 | 12:31 | | | | 9951 | | | | | | | | |
| X 90 | E 81 | | | 12:38 | 12:46 | | | | 10079 | chop increasing on x tie | | | | | | | |

| axis geospatial | | | | LiDAR and Imagery Flight Report | | | | Project(s): | | 201010-2101 NV MTN | | | |
|--------------------|-----------|----------------------|------|---------------------------------|---------------|--------------------|-------------------|------------------------|---------------------|-----------------------|--------|----------|---------------|
| Pilot: | | ES | | Project Number(s): | | 201010-2101 NV | | | Date: | 7/28/2022 | | | |
| Operator: | | AC | | Project Name(s): | | | | | Mission Start (LT): | 1223.0 | | | |
| Aircraft: | | 359RX | | Hobbs Start: | 1222.4 | Hobbs Stop: | | | Mission End (LT): | 1228.3 | | | |
| LiDAR Unit: | | 3) VQ-1560i S2223544 | | Scan Rate: | | 2*144 | | Camera Unit: | Phase One | Drive: | A 0/1 | | |
| MTA Zones: | | 44602 | | Grnd Spd Max (kts): | | 150 | | FOV (deg): | 58.52 | Sun Angle: | | | |
| PRR (kHz): | | 2*1000 | | Altitude (feet AMT): | | 4200 | | Lateral Overlap (%): | 30% | Lens: | | | |
| Laser Power (%): | | 100 | | Point Spacing (m): | | 0.321 | | Forward Overlap (%): | | Point Density (ppms): | 5.88 | | |
| | | Camera Counter | | Line Start/Stop | | | | | | | | | |
| Line # | Direction | To | From | Start Time UTC | Stop Time UTC | Altitude (Planned) | Altitude (Actual) | Remarks | | | Clouds | Aperture | Shutter Speed |
| 79 | N | | | 13:38 | 13:49 | 9555+- | | BILLINGS EAST REFLIGHT | | | | | |
| 80 | S | | | 13:54 | 14:06 | | | BILLINGS EAST REFLIGHT | | | | | |
| 87 | N | | | 14:10 | 14:17 | | | BILLINGS EAST REFLIGHT | | | | | |
| 88 | S | | | 14:22 | 14:24 | | | BILLINGS EAST REFLIGHT | | | | | |
| 89 XTE | W | | | 14:30 | 14:34 | | | | | | | | |
| 21 | S | | | 14:48 | 14:56 | | | | | | | | |
| 19 | N | | | 15:00 | 15:05 | | | | | | | | |
| 17 | S | | | 15:11 | 15:17 | | | | | | | | |
| 15 | N | | | 15:20 | 15:28 | | | | | | | | |
| 13 | S | | | 15:31 | 15:36 | | | | | | | | |
| 11 | N | | | 15:43 | 15:50 | | | | | | | | |
| 10 | S | | | 15:54 | 16:01 | | | | | | | | |
| 9 | N | | | 16:04 | 16:10 | | | | | | | | |
| 8 | S | | | 16:13 | 16:19 | | | | | | | | |
| 7 | N | | | 16:23 | 16:28 | | | | | | | | |
| 6 | S | | | 16:32 | 16:37 | | | | | | | | |
| 5 | N | | | 16:42 | 16:47 | | | | | | | | |
| 4 | S | | | 16:52 | 16:59 | | | | | | | | |
| 3 | N | | | 17:03 | 17:07 | | | | | | | | |
| 2 | S | | | 17:11 | 17:15 | | | | | | | | |
| 1 | N | | | 17:19 | 17:22 | | | | | | | | |
| 63 | W | | | 17:32 | 17:39 | | | BILLINGS WEST | | | | | |
| 62 | E | | | 17:41 | 17:49 | | | | | | | | |
| 61 | W | | | 17:52 | 17:57 | | | | | | | | |
| 60 | E | | | 17:59 | 18:04 | | | | | | | | |
| 68 XTE | S | | | 18:09 | 18:22 | | | | | | | | |
| 90 XTE | E | | | 18:26 | 18:38 | | | | | | | | |

| axis geospatial | | | LiDAR and Imagery Flight Report | | | | Project(s): | | 2007821B MONTANT | | | | |
|--------------------|----------------------|----|---------------------------------|----------------|----------------------|--------------------|-----------------------|---------------------|------------------|--|--------|----------|---------------|
| Pilot: | ES | | Project Number(s): | | 2007821B MONTANT | | | Date: | 7/29/2022 | | | | |
| Operator: | AC | | Project Name(s): | | | | | Mission Start (LT): | 3224.5 | | | | |
| Aircraft: | 89LT | | Hobbs Start: | 3224.1 | Hobbs Stop: | 3226.8 | Mission End (LT): | 3226.3 | | | | | |
| LiDAR Unit: | 2) VQ-1560i S2222593 | | Scan Rate: | 2*144 | Camera Unit: | Phase One | Drive: | A 0/1 | | | | | |
| MTA Zones: | 6-Apr | | Grnd Spd Max (kts): | 155 | FOV (deg): | 58.52 | Sun Angle: | | | | | | |
| PRR (kHz): | 2*700 | | Altitude (feet AMT): | 5500 | Lateral Overlap (%): | 30% | Lens: | | | | | | |
| Laser Power (%): | 100 | | Point Spacing (m): | 0.321 | Forward Overlap (%): | | Point Density (ppms): | 5.88 | | | | | |
| | Camera Counter | | Line Start/Stop | | | | | | | | | | |
| Line # | Direction | To | From | Start Time UTC | Stop Time UTC | Altitude (Planned) | Altitude (Actual) | Remarks | | | Clouds | Aperture | Shutter Speed |
| 83 XTIE | N | | | 16:36 | 16:38 | | | | | | | | |
| 69 | W | | | 16:45 | 16:57 | | | | | | | | |
| 70 | E | | | 16:59 | 17:09 | | | | | | | | |
| 71 | W | | | 17:12 | 17:22 | | | | | | | | |
| 72 | E | | | 17:25 | 17:34 | | | | | | | | |
| 73 | W | | | 17:38 | 17:48 | | | | | | | | |
| 74 | E | | | 17:52 | 18:00 | | | TURBULENCE | | | | | |
| 75 | W | | | 18:03 | 18:12 | | | TURBULENCE | | | | | |
| 76 | E | | | 14:14 | 14:22 | | | TURBULENCE | | | | | |

| axis geospatial | | | LiDAR and Imagery Flight Report | | | | Project(s): | | 2007821B MONTANT | | | | |
|--------------------|----------------------|----|---------------------------------|----------------|----------------------|--------------------|-----------------------|---------------------|------------------|--|--------|----------|---------------|
| Pilot: | ES | | Project Number(s): | | 2007821B MONTANT | | | Date: | 7/30/2022 | | | | |
| Operator: | AC | | Project Name(s): | | | | | Mission Start (LT): | 3227.5 | | | | |
| Aircraft: | 89LT | | Hobbs Start: | 3226.8 | Hobbs Stop: | | Mission End (LT): | 3231.0 | | | | | |
| LiDAR Unit: | 2) VQ-1560i S2222593 | | Scan Rate: | 2*144 | Camera Unit: | Phase One | Drive: | A 0/1 | | | | | |
| MTA Zones: | 6 - 10 | | Grnd Spd Max (kts): | 155 | FOV (deg): | 58.52 | Sun Angle: | | | | | | |
| PRR (kHz): | 2*700 | | Altitude (feet AMT): | 5500 | Lateral Overlap (%): | 30% | Lens: | | | | | | |
| Laser Power (%): | 100 | | Point Spacing (m): | 0.321 | Forward Overlap (%): | | Point Density (ppms): | 5.88 | | | | | |
| | Camera Counter | | Line Start/Stop | | | | | | | | | | |
| Line # | Direction | To | From | Start Time UTC | Stop Time UTC | Altitude (Planned) | Altitude (Actual) | Remarks | | | Clouds | Aperture | Shutter Speed |
| 77 | W | | | 13:37 | 13:48 | 10215+- | | | | | | | |
| 78 | E | | | 13:50 | 13:58 | | | | | | | | |
| 79 | W | | | 14:02 | 14:11 | | | | | | | | |
| 80 | E | | | 14:14 | 14:22 | | | | | | | | |
| 81 | W | | | 14:27 | 14:37 | | | | | | | | |
| 82 | E | | | 14:39 | 14:47 | | | | | | | | |
| XTIE | N | | | 14:54 | 14:57 | | | | | | | | |
| XTIE | W | | | 15:03 | 15:14 | | | | | | | | |
| 1 | S | | | 15:22 | 15:29 | | | | | | | | |
| 2 | N | | | 15:32 | 15:40 | | | | | | | | |
| 3 | S | | | 15:43 | 15:51 | | | | | | | | |
| 4 | N | | | 15:55 | 16:06 | | | LIGHT TURBULENCE | | | | | |
| 5 | S | | | 16:09 | 16:19 | | | | | | | | |
| 6 | N | | | 16:22 | 16:34 | | | MODERATE TURBULENCE | | | | | |
| 7 | S | | | 16:35 | 16:46 | | | | | | | | |
| 8 | N | | | 16:50 | 17:03 | | | CALLING IT | | | | | |

| axis geospatial | | | | LiDAR and Imagery Flight Report | | | | Project(s): | | 2007821B MONTANT | | | |
|--------------------|-----------|----------------------|------|---------------------------------|-----------------|--------------------|-------------------|---------------------------------|---------------------|-----------------------|--------|----------|---------------|
| Pilot: | | ES | | Project Number(s): | | 2007821B MONTANT | | | Date: | 7/31/2022 | | | |
| Operator: | | AC | | Project Name(s): | | | | | Mission Start (LT): | 3232.1 / 3236.5 | | | |
| Aircraft: | | 89LT | | Hobbs Start: | 3231.5 / 3236.0 | Hobbs Stop: | 3236.0 / 3237.9 | Mission End (LT): | 3235.7 / 3237.7 | | | | |
| LiDAR Unit: | | 2) VQ-1560i S2222593 | | Scan Rate: | | 2*144 | | Camera Unit: | Phase One | Drive: | A 0/1 | | |
| MTA Zones: | | 6 - 10 | | Grnd Spd Max (kts): | | 155 | | FOV (deg): | 58.52 | Sun Angle: | | | |
| PRR (kHz): | | 2*700 | | Altitude (feet AMT): | | 5500 | | Lateral Overlap (%): | 30% | Lens: | | | |
| Laser Power (%): | | 100 | | Point Spacing (m): | | 0.321 | | Forward Overlap (%): | | Point Density (ppms): | 5.88 | | |
| | | Camera Counter | | Line Start/Stop | | | | | | | | | |
| Line # | Direction | To | From | Start Time UTC | Stop Time UTC | Altitude (Planned) | Altitude (Actual) | Remarks | | | Clouds | Aperture | Shutter Speed |
| 9 | N | | | 13:34 | 13:52 | 10560+- | | THICK SMOKE FROM FIRE NORTH END | | | | | |
| XTIE | E | | | 13:55 | 13:52 | | | VERY THICK SMOKE EXAMPLE | | | | | |
| 10 | S | | | 14:10 | 14:28 | | | THICK SMOKE FROM FIRE NORTH END | | | | | |
| 57 | N | | | 14:41 | 14:50 | 10090+- | | | | | | | |
| 56 | S | | | 14:53 | 15:02 | | | | | | | | |
| 55 | N | | | 15:06 | 15:14 | | | | | | | | |
| 54 | S | | | 15:18 | 15:27 | | | | | | | | |
| 53 | N | | | 15:30 | 15:30 | | | | | | | | |
| 52 | S | | | 15:42 | 15:50 | | | | | | | | |
| 51 | N | | | 15:55 | 16:04 | | | | | | | | |
| 50 | S | | | 16:08 | 16:16 | | | | | | | | |
| 49 | N | | | 16:20 | 16:29 | | | | | | | | |
| 48 | S | | | 16:33 | 16:41 | | | | | | | | |
| 47 | N | | | 16:44 | 16:54 | | | | | | | | |
| XTIE | E | | | 16:59 | 16:03 | | | | | | | | |
| 1 | W | | | 18:44 | 18:48 | 7860+- | | | | | | | |
| 2 | E | | | 18:50 | 18:52 | | | | | | | | |
| 3 | W | | | 18:56 | 18:59 | | | | | | | | |
| 4 | E | | | 19:02 | 19:07 | | | | | | | | |
| 5 | W | | | 19:09 | 19:12 | | | | | | | | |
| 6 | E | | | 19:15 | 19:18 | | | | | | | | |
| 7 | W | | | 19:21 | 19:24 | | | | | | | | |
| 8 | E | | | 19:31 | 19:34 | | | | | | | | |
| XTIE | N | | | 19:39 | 19:42 | | | | | | | | |

| axis geospatial | | | | LiDAR and Imagery Flight Report | | | | Project(s): 2007821B MONTANT | | | | |
|--------------------|-----------|----------------------|------|---------------------------------|------------------|--------------------|-------------------|---|-----------------------|--|--|--|
| Pilot: | | ES | | Project Number(s): | | 2007821B MONTANT | | Date: | 8/1/2022 | | | |
| Operator: | | AC | | Project Name(s): | | | | Mission Start (LT): | 3238.3 | | | |
| Aircraft: | | 89LT | | Hobbs Start: | 3237.9 | Hobbs Stop: | 3241.9 | Mission End (LT): | 3241.7 | | | |
| LiDAR Unit: | | 2) VQ-1560i S2222593 | | Scan Rate: | | 2*144 | | Camera Unit: | Phase One | | | |
| MTA Zones: | | 6 - 10 | | Grnd Spd Max (kts): | | 155 | | FOV (deg): | 58.52 | | | |
| PRR (kHz): | | 2*1000 | | Altitude (feet AMT): | | 5500 | | Lateral Overlap (%): | 30% | | | |
| Laser Power (%): | | 100 | | Point Spacing (m): | | 0.321 | | Forward Overlap (%): | Point Density (ppms): | | | |
| | | | | | | | | 5.88 | | | | |
| | | Camera Counter | | Line Start/Stop | | | | | | | | |
| Line # | Direction | N+A32: B35 | From | Start Time UTC | Stop Time UTC | Altitude (Planned) | Altitude (Actual) | Remarks | | | | |
| 9 | E | | | 13:28 | 13:35 | 7860+- | | | | | | |
| 10 | W | | | 13:39 | 13:49 | | | | | | | |
| 11 | E | | | 13:52 | 13:59 | | | | | | | |
| 12 | W | | | 14:03 | 14:13 | | | | | | | |
| 13 | E | | | 14:16 | 14:22 | | | | | | | |
| 14 | W | | | 14:26 | 14:36 | | | | | | | |
| 15 | E | | | 14:39 | 14:46 | | | | | | | |
| 16 | W | | | 14:50 | 14:59 | | | | | | | |
| 17 | E | | | 15:02 | 15:10 | | | | | | | |
| 18 | W | | | 15:12 | 15:24 | | | | | | | |
| 19 | E | | | 15:27 | 15:33 | | | | | | | |
| 20 | W | | | 15:39 | 15:48 | | | | | | | |
| 21 | E | | | 15:52 | 15:58 | | | | | | | |
| 22 | W | | | 16:02 | 16:13 | | | LIGHT TURBULENCE | | | | |
| 23 | E | | | 16:16 | 16:21 | | | LIGHT TURBULENCE | | | | |
| 24 | W | | | 16:28 | 16:37 | | | MODERATE TURBULENCE WITH UP/DOWN DRAFTS | | | | |
| XTE | N | | | 16:41 | 16:46 | | | | | | | |

| axis geospatial | | | | LiDAR and Imagery Flight Report | | | | Project(s): 2007821B MONTANT QL2 BILLINGS WEST | | |
|--------------------|-----------|----------------------|------|---------------------------------|------------------|----------------------|-------------------|--|-----------------------|--------------|
| Pilot: | | ES | | Project Number(s): | | 2007821B MONTANT QL2 | | Date: | 8/4/2022 | |
| Operator: | | AC | | Project Name(s): | | | | Mission Start (LT): | 3247.0 | |
| Aircraft: | | 89LT | | Hobbs Start: | 3246.1 | Hobbs Stop: | | Mission End (LT): | 3251.0 | |
| LiDAR Unit: | | 2) VQ-1560i S2222593 | | Scan Rate: | | 2*144 | | Camera Unit: | Phase One | |
| MTA Zones: | | 6 - 10 | | Grnd Spd Max (kts): | | 150 | | FOV (deg): | 58.52 | |
| PRR (kHz): | | 2*700 | | Altitude (feet AMT): | | 4200 | | Lateral Overlap (%): | 30% | |
| Laser Power (%): | | 100 | | Point Spacing (m): | | 0.321 | | Forward Overlap (%): | Point Density (ppms): | |
| | | Camera Counter | | Line Start/Stop | | MOB: | -3250.1 | MSN: | 4.0 | TOT: -3246.1 |
| Line # | Direction | N+A32:B 35 | From | Start Time UTC | Stop Time UTC | Altitude (Planned) | Altitude (Actual) | Remarks | | |
| 11 | S | | | 14:16 | 14:33 | 10465+- | | QL2 BILLINGS WEST | | |
| 12 | N | | | 14:35 | 14:51 | | | | | |
| 13 | S | | | 15:02 | 15:17 | | | | | |
| 14 | N | | | 15:20 | 15:35 | | | | | |
| 15 | S | | | 15:39 | 15:55 | | | | | |
| 16 | N | | | 15:57 | 16:12 | | | | | |
| 17 | S | | | 16:15 | 16:29 | | | | | |
| 18 | N | | | 16:32 | 16:47 | | | | | |
| 19 | S | | | 16:50 | 17:05 | | | | | |
| 20 | N | | | 17:09 | 17:25 | | | LIGHT TURBULENCE | | |
| 21 | S | | | 17:27 | 17:41 | | | | | |
| 22 | N | | | 17:44 | 17:57 | | | MODERATE TURBULENCE | | |
| XTE | W | | | 18:04 | 18:11 | | | | | |

| axis geospatial | | | | LiDAR and Imagery Flight Report | | | | | Project(s): 2007821B MONTANT QL2 BILLINGS WEST | | | | |
|--------------------|-----------|----------------------|------|---------------------------------|---------------|--|-------------------|----------------------|--|----------|--------|----------|---------------|
| Pilot: | | ES | | Project Number(s): | | 2007821B MONTANT QL2 | | | Date: | 8/5/2022 | | | |
| Operator: | | AC | | Project Name(s): | | | | | Mission Start (LT): | 1229.9 | | | |
| Aircraft: | | N359RX | | Hobbs Start: | 1229.4 | Hobbs Stop: | | | Mission End (LT): | 1234.8 | | | |
| LiDAR Unit: | | 2) VQ-1560i S2222593 | | Scan Rate: | | 2*144 | | Camera Unit: | Phase One | | | | |
| MTA Zones: | | 6 - 10 | | Grnd Spd Max (kts): | | 155 | | FOV (deg): | 58.52 | | | | |
| PRR (kHz): | | 2*700 | | Altitude (feet AMT): | | 5985 | | Lateral Overlap (%): | 30% | | | | |
| Laser Power (%): | | 100 | | Point Spacing (m): | | 0.321 | | Forward Overlap (%): | Point Density (ppms): | | | | |
| | | | | | | | | | 5.88 | | | | |
| | | | | Camera Counter | | Line Start/Stop | | MOB: | -1234.3 | MSN: | 4.9 | | |
| | | | | Line Start/Stop | | MOB: | | TOT: | -1229.4 | | | | |
| Line # | Direction | To | From | Start Time UTC | Stop Time UTC | Altitude (Planned) | Altitude (Actual) | Remarks | | | Clouds | Aperture | Shutter Speed |
| 23 | S | | | 14:34 | 14:46 | 10630+- | | QL2 BILLINGS WEST | | | | | |
| 24 | N | | | 14:49 | 15:02 | | | | | | | | |
| 25 | S | | | 15:06 | 15:20 | LOST BOTH CHANNELS SOUTH END OF LINE / COULD NOT GET CHANNEL 1 BACK / HAD TO REBOOT THE SYSTEM | | | | | | | |
| 26 | S | | | 15:39 | 15:52 | | | | | | | | |
| 25 | N | | | 15:55 | 15:57 | | | | | | | | |
| 27 | N | | | 16:03 | 16:15 | | | | | | | | |
| 28 | N | | | 16:39 | 16:51 | | | | | | | | |
| 29 | S | | | 16:54 | 17:06 | | | | | | | | |
| 30 | N | | | 17:09 | 17:21 | | | | | | | | |
| 31 | S | | | 17:24 | 17:38 | | | | | | | | |
| 32 | N | | | 17:40 | 17:51 | | | | | | | | |
| 33 | S | | | 17:55 | 18:08 | | | | | | | | |
| 34 | N | | | 18:11 | 18:25 | | | | | | | | |
| 35 | S | | | 18:27 | 18:39 | | | | | | | | |
| 36 | N | | | 18:42 | 18:53 | | | | | | | | |
| XTIE | W | | | 19:07 | 19:11 | | | | | | | | |

| axis geospatial | | | | LiDAR and Imagery Flight Report | | | | | Project(s): 2007821B MONTANT QL2 BILLINGS WEST | | | | |
|--------------------|-----------|----------------------|------|---------------------------------|---------------|----------------------|-------------------|----------------------|--|----------|--------|----------|---------------|
| Pilot: | | ES | | Project Number(s): | | 2007821B MONTANT QL2 | | | Date: | 8/9/2022 | | | |
| Operator: | | AC | | Project Name(s): | | | | | Mission Start (LT): | 1236.3 | | | |
| Aircraft: | | N359RX | | Hobbs Start: | 1235.8 | Hobbs Stop: | | | Mission End (LT): | 1239.0 | | | |
| LiDAR Unit: | | 2) VQ-1560i S2222593 | | Scan Rate: | | 2*144 | | Camera Unit: | Phase One | | | | |
| MTA Zones: | | 6 - 10 | | Grnd Spd Max (kts): | | 155 | | FOV (deg): | 58.52 | | | | |
| PRR (kHz): | | 2*700 | | Altitude (feet AMT): | | 5985 | | Lateral Overlap (%): | 30% | | | | |
| Laser Power (%): | | 100 | | Point Spacing (m): | | 0.321 | | Forward Overlap (%): | Point Density (ppms): | | | | |
| | | | | Camera Counter | | Line Start/Stop | | MOB: | -1238.5 | MSN: | 2.7 | | |
| | | | | Line Start/Stop | | MOB: | | TOT: | -1235.8 | | | | |
| Line # | Direction | To | From | Start Time UTC | Stop Time UTC | Altitude (Planned) | Altitude (Actual) | Remarks | | | Clouds | Aperture | Shutter Speed |
| 37 | S | | | 13:58 | 14:12 | 10630+- | | QL2 BILLINGS WEST | | | | | |
| 38 | N | | | 14:16 | 14:27 | | | | | | | | |
| 39 | S | | | 14:00 | 14:43 | | | | | | | | |
| 40 | N | | | 14:48 | 15:00 | | | | | | | | |
| 41 | S | | | 15:04 | 15:17 | | | | | | | | |
| 42 | N | | | 15:20 | 15:32 | | | | | | | | |
| 43 | S | | | 15:36 | 15:48 | | | | | | | | |
| 44 | N | | | 15:51 | 16:02 | | | | | | | | |
| 45 | S | | | 16:07 | 16:18 | | | | | | | | |
| 46 | N | | | 16:20 | 16:32 | | | | | | | | |
| XTIE | W | | | 16:36 | 16:42 | | | | | | | | |

POSPac Graphics


Mission Information

| | |
|------------------|---------------------|
| Project name | VQ2_20220630_1 |
| Processing date | 2022-08-26 19:46:25 |
| Mission date | 2022-06-30 13:35:38 |
| Mission duration | 05:42:22.000 |
| Processing mode | IN-Fusion PP-RTX |


Rover Hardware Information

| | |
|---------------|--------------------------|
| Product | POS AV 610 VER6 Hw2.5-12 |
| Serial number | S/N8223 |
| IMU type | S7 |
| Receiver type | BD982 |
| Antenna type | AV37 |

Forward/Reverse Separation



Estimated Position Accuracy




Mission Information

| | |
|------------------|---------------------|
| Project name | V02_20220709 |
| Processing date | 2022-08-26 19:51:19 |
| Mission date | 2022-07-08 17:27:06 |
| Mission duration | 05:14:20.000 |
| Processing mode | IN-Fusion PP-RTX |


Rover Hardware Information

| | |
|---------------|--------------------------|
| Product | POS AV 610 VER6 HW2.5-12 |
| Serial number | S/N8223 |
| IMU type | 57 |
| Receiver type | BD982 |
| Antenna type | AV37 |

Forward/Reverse Separation



Estimated Position Accuracy




Mission Information

| | |
|------------------|---------------------------------------|
| Project name | 20078-21b_N89LT-S2222593-X_20220709_1 |
| Processing date | 2022-07-28 14:51:17 |
| Mission date | 2022-07-09 13:42:09 |
| Mission duration | 05:55:01.000 |
| Processing mode | IN-Fusion PP-RTK |


Rover Hardware Information

| | |
|---------------|--------------------------|
| Product | POS AV 610 VER6 HW2.5-12 |
| Serial number | S/N8223 |
| IMU type | 57 |
| Receiver type | BD962 |
| Antenna type | AV37 |

Forward/Reverse Separation



Estimated Position Accuracy




Mission Information

| | |
|------------------|---------------------------------------|
| Project name | 20078-21b_N89LT-S2222593-X_20220709_2 |
| Processing date | 2022-07-28 14:50:33 |
| Mission date | 2022-07-09 20:35:34 |
| Mission duration | 02:00:36.000 |
| Processing mode | IN-Fusion PP-RTX |


Rover Hardware Information

| | |
|---------------|--------------------------|
| Product | POS AV 610 VER6 HW2.5-12 |
| Serial number | S/N8223 |
| IMU type | 57 |
| Receiver type | BD982 |
| Antenna type | AV37 |

Forward/Reverse Separation



Estimated Position Accuracy




Mission Information

| | |
|------------------|---------------------------------------|
| Project name | 20078_20220710_LT_S2222593_STATIC_RTX |
| Processing date | 2022-07-22 17:24:55 |
| Mission date | 2022-07-10 13:51:36 |
| Mission duration | 05:21:45.000 |
| Processing mode | IN-Fusion PP-RTX |


Rover Hardware Information

| | |
|---------------|--------------------------|
| Product | POS AV 610 VER6 HW2.5-12 |
| Serial number | S/N8223 |
| IMU type | 57 |
| Receiver type | BD982 |
| Antenna type | AV37 |

Forward/Reverse Separation



Estimated Position Accuracy




Mission Information

| | |
|------------------|---------------------------------------|
| Project name | 20078_20220712_LT_S2222593_STATIC_RTX |
| Processing date | 2022-07-26 15:58:55 |
| Mission date | 2022-07-12 13:49:17 |
| Mission duration | 05:08:29.824 |
| Processing mode | IN-Fusion PP-RTX |


Rover Hardware Information

| | |
|---------------|--------------------------|
| Product | POS AV 610 VER6 HW2.5-12 |
| Serial number | S/N8223 |
| IMU type | 57 |
| Receiver type | BD982 |
| Antenna type | AV37 |

Forward/Reverse Separation



Estimated Position Accuracy



Mission Information

| | |
|------------------|-------------------------------------|
| Project name | 20078-21b_N89LT-S2222593-X_20220713 |
| Processing date | 2022-08-04 13:57:52 |
| Mission date | 2022-07-13 13:45:27 |
| Mission duration | 05:15:49.000 |
| Processing mode | IN-Fusion PP-RTX |


Rover Hardware Information

| | |
|---------------|--------------------------|
| Product | POS AV 610 VER6 HW2.5-12 |
| Serial number | S/N8223 |
| IMU type | 57 |
| Receiver type | BD982 |
| Antenna type | AV37 |

Forward/Reverse Separation



Estimated Position Accuracy




Mission Information

| | |
|------------------|------------------------------------|
| Project name | 20078_20220728_RX_52223544_GSM_RTX |
| Processing date | 2022-08-01 22:21:54 |
| Mission date | 2022-05-23 11:51:21 |
| Mission duration | 05:27:10.000 |
| Processing mode | IN-Fusion PP-RTX |


Rover Hardware Information

| | |
|---------------|--------------------------|
| Product | POS AV 610 VER6 HW2.5-12 |
| Serial number | S/N9865 |
| IMU type | 57 |
| Receiver type | BD982 |
| Antenna type | AV37 |

Forward/Reverse Separation



Estimated Position Accuracy




Mission Information

| | |
|------------------|-------------------------------------|
| Project name | 20078-21b_N89LT-S2222593-X_20220729 |
| Processing date | 2022-08-10 15:02:37 |
| Mission date | 2022-07-29 15:55:18 |
| Mission duration | 02:41:50.000 |
| Processing mode | IN-Fusion PP-RTX |


Rover Hardware Information

| | |
|---------------|--------------------------|
| Product | POS AV 610 VER6 HW2.5-12 |
| Serial number | S/N8223 |
| IMU type | 57 |
| Receiver type | BD982 |
| Antenna type | AV37 |

Forward/Reverse Separation



Estimated Position Accuracy




Mission Information

| | |
|------------------|---------------------|
| Project name | VQ2_20220730 |
| Processing date | 2022-08-26 19:47:43 |
| Mission date | 2022-07-30 13:02:45 |
| Mission duration | 04:27:19.000 |
| Processing mode | IN-Fusion PP-RTX |


Rover Hardware Information

| | |
|---------------|--------------------------|
| Product | POS AV 610 VER6 HW2.5-12 |
| Serial number | S/N8223 |
| IMU type | 57 |
| Receiver type | BD982 |
| Antenna type | AV37 |

Forward/Reverse Separation



Estimated Position Accuracy




Mission Information

| | |
|------------------|---------------------------------------|
| Project name | 20078_20220731_LT_S2222593_STATIC_RTX |
| Processing date | 2022-08-03 20:05:52 |
| Mission date | 2022-07-31 13:30:58 |
| Mission duration | 03:36:42.000 |
| Processing mode | IN-Fusion PP-RTX |


Rover Hardware Information

| | |
|---------------|--------------------------|
| Product | POS AV 610 VER6 HW2.5-12 |
| Serial number | S/N8223 |
| IMU type | 57 |
| Receiver type | BD982 |
| Antenna type | AV37 |

Forward/Reverse Separation



Estimated Position Accuracy




Mission Information

| | |
|------------------|---|
| Project name | 20078_20220731-2_LT_S2222593_STATIC_RTX |
| Processing date | 2022-08-03 21:12:02 |
| Mission date | 2022-07-31 18:27:04 |
| Mission duration | 01:26:35.972 |
| Processing mode | IN-Fusion PP-RTX |


Rover Hardware Information

| | |
|---------------|--------------------------|
| Product | POS AV 610 VER6 HW2.5-12 |
| Serial number | S/N8223 |
| IMU type | 57 |
| Receiver type | BD982 |
| Antenna type | AV37 |

Forward/Reverse Separation



Estimated Position Accuracy




Mission Information

| | |
|------------------|----------------------------|
| Project name | 20078_20220801_LT_S2222593 |
| Processing date | 2023-05-11 21:37:08 |
| Mission date | 2022-08-01 13:16:38 |
| Mission duration | 03:38:35.000 |
| Processing mode | IN-Fusion PP-RTX |


Rover Hardware Information

| | |
|---------------|--------------------------|
| Product | POS AV 610 VER6 HW2.5-12 |
| Serial number | S/N8223 |
| IMU type | 57 |
| Receiver type | BD982 |
| Antenna type | AV37 |

Forward/Reverse Separation



Estimated Position Accuracy



Mission Information

| | |
|------------------|--|
| Project name | 20078-21b_N89LT-S2222593-X_20220804_PP-RTX |
| Processing date | 2022-08-16 17:28:47 |
| Mission date | 2022-08-04 13:25:50 |
| Mission duration | 04:55:36.000 |
| Processing mode | IN-Fusion PP-RTX |


Rover Hardware Information

| | |
|---------------|--------------------------|
| Product | POS AV 610 VER6 HW2.5-12 |
| Serial number | S/N8223 |
| IMU type | 57 |
| Receiver type | BD982 |
| Antenna type | AV37 |

Forward/Reverse Separation



Estimated Position Accuracy




Mission Information

| | |
|------------------|---------------------|
| Project name | Flight_1_VQ3_RX |
| Processing date | 2022-08-26 19:48:34 |
| Mission date | 2022-08-05 13:58:01 |
| Mission duration | 01:24:35.000 |
| Processing mode | IN-Fusion PP-RTX |


Rover Hardware Information

| | |
|---------------|--------------------------|
| Product | POS AV 610 VER6 HW2.5-12 |
| Serial number | S/N9865 |
| IMU type | 57 |
| Receiver type | BD982 |
| Antenna type | AV37 |

Forward/Reverse Separation



Estimated Position Accuracy




Mission Information

| | |
|------------------|---------------------|
| Project name | Flight_2_VQ3_RX |
| Processing date | 2022-08-26 19:48:41 |
| Mission date | 2022-08-05 15:27:28 |
| Mission duration | 00:57:33.000 |
| Processing mode | IN-Fusion PP-RTX |


Rover Hardware Information

| | |
|---------------|--------------------------|
| Product | POS AV 610 VER6 HW2.5-12 |
| Serial number | S/N9865 |
| IMU type | 57 |
| Receiver type | BD982 |
| Antenna type | AV37 |

Forward/Reverse Separation



Estimated Position Accuracy




Mission Information

| | |
|------------------|---------------------|
| Project name | Flight_3_VQ3_RX |
| Processing date | 2022-08-26 19:48:21 |
| Mission date | 2022-08-05 16:36:02 |
| Mission duration | 02:53:44.000 |
| Processing mode | IN-Fusion PP-RTX |


Rover Hardware Information

| | |
|---------------|--------------------------|
| Product | POS AV 610 VER6 HW2.5-12 |
| Serial number | S/N9865 |
| IMU type | 57 |
| Receiver type | BD982 |
| Antenna type | AV37 |

Forward/Reverse Separation



Estimated Position Accuracy




Mission Information

| | |
|------------------|----------------------------|
| Project name | 20078_20220809_RX_S2223544 |
| Processing date | 2022-08-12 15:20:04 |
| Mission date | 2022-05-23 11:51:21 |
| Mission duration | 03:10:09.000 |
| Processing mode | IN-Fusion PP-RTX |

Rover Hardware Information

| | |
|---------------|--------------------------|
| Product | POS AV 610 VER6 HW2.5-12 |
| Serial number | S/N9865 |
| IMU type | 57 |
| Receiver type | BD982 |
| Antenna type | AV37 |

Forward/Reverse Separation



Estimated Position Accuracy

